

Segmental Bridge Construction Techniques

Presented by: Bob Sward

2012 PTI Convention

Nashville, TN

May 7, 2012





Segmental Bridge Construction Techniques

- Cast In Place
 - Travelers
 - Incremental Launching
- Precast Segmental
 - Casting Yard
 - Cantilever Construction
 - Span by Span
 - Full Span




Cast in Place Segmental - Cantilever

- Span Length 300 to 800 ft
- Typical Segment Length 16 ft
- Non Linear Construction
- Minimal Crane Capacity
- Composite Crew - Efficiency
- Typical Cycle Time – 5 days



Cast in Place Segmental - Cantilever



Cast in Place Segmental - Cantilever




4th Street Bridge – Pueblo, CO



Ilan Bridge, Taiwan
(Max. segment weight 120t, FT steel weight 55t)




H-3 North Halawa Valley Viaduct - Hawaii
(1990-1992)




Cast-in-Place – Incremental Launching

- Span Lengths 200' – 350'
- Casting/launching from end of bridge working from the ground
- Relatively standard forming
- 7 day cycle per launch




TYPICAL CONSTRUCTION SEQUENCE




Cast-in-Place – Incremental Launching



Typical Construction Cycle	Duration: 8-Day Cycle (Days)							
Description	1	2	3	4	5	6	7	8
Launch Segment								
Strip and Clean Forms								
Install Base and Web Rebar								
Install Web Forms								
Concrete Base and Webs								
Install Inner Forms								
Install Top Slab Rebar								
Concrete Top Slab								
Curing								
Stress P.T.								



TYPICAL CONSTRUCTION SEQUENCE




Precast Segmental

- Segment Casting



Precast Segmental

- Casting Yard




DUBAI METRO PROJECT

- One of the largest pre-casting yards in the world
- 9 tower cranes, 11 gantry cranes, 64 casting forms, 2,500 segment storage
- Camp for 3,500+ staff & crew

Precast Segmental – Cantilever

Erection with Launching Gantry


- Span up to 350 ft±
- Speed of Erection (up to 6 pairs of segments)
- Delivery from behind or below
- Overhead Construction
- Self Launching – min. crane support
- Parallel Structures Simultaneously
- Temp loads directly into Piers
- Limited horizontal curvature



Precast Segmental – Cantilever

Erection with Lifting Frames


- Longer Span Lengths
- Larger Segments
- Deck Construction can be non-linear (multiple work fronts)
- Simple Erection Works
- Rapid Construction



Precast Segmental – Cantilever

Erection with Lifting Frames

- Longer Span Lengths
- Larger Segments
- Deck Construction can be non-linear (multiple work fronts)
- Simple Erection Works
- Rapid Construction




Precast Segmental – Cantilever

Erection with Lifting Frames

- Longer Span Lengths
- Larger Segments
- Deck Construction can be non-linear (multiple work fronts)
- Simple Erection Works
- Rapid Construction


Typical Erection Cycle	Duration: 13 Shifts												
Description	1	2	3	4	5	6	7	8	9	10	11	12	13
Erect & Assemble Lifting Frames & Brackets on Pier Head													
Segment Erection - Pair 1													
Wet Joint Construction													
Wet Joint Curing													
Segment Erection - Pair 2-3													
Segment Erection - Pair 4-5													
Segment Erection - Pair 6-7													
Segment Erection - Pair 8-9													
Segment Erection - Pair 10-11													
Segment Erection - Pair 12-13													
Remove Lifting Frames													



Precast Segmental – Cantilever

Erection with Cranes

- Longer Span Lengths
- Smaller Segments
- Deck Construction can be non-linear (multiple work fronts)
- Readily Available Equipment
- Rapid Construction
- Small Erection Crew




Precast Segmental – Cantilever

Erection with Cranes

- Longer Span Lengths
- Smaller Segments
- Deck Construction can be non-linear (multiple work fronts)
- Readily Available Equipment
- Rapid Construction
- Small Erection Crew


Typical Erection Cycle	Duration: 8 Shifts							
Description	1	2	3	4	5	6	7	8
Installation of Pier Segment Support Brackets								
Installation of Pier Segment								
Segment Erection - Pair 1-3								
Segment Erection - Pair 4-6								
Segment Erection - Pair 7-9								
Segment Erection - Pair 10-12								



Precast Segmental – Span-by-Span

Erection with Launching Gantry (Overhead or Underslung)

- Spans typically < 170 ft
- Speed of Erection
(1 span per day possible)
- Small Crew
- Delivery from behind or below
- Temp load directly into Piers




Precast Segmental – Span-by-Span

Erection with Launching Gantry (Overhead or Underslung)

- Spans typically < 170 ft
- Speed of Erection
(1 span per day possible)
- Small Crew
- Delivery from behind or below
- Temp load directly into Piers


Typical Erection Cycle	Duration: 4-Day Cycle							
Description	1		2		3		4	
	D/S	N/S	D/S	N/S	D/S	N/S	D/S	N/S
Launching of Gantry	Red	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow
Segment Placing	Yellow	Red	Red	Yellow	Yellow	Yellow	Yellow	Yellow
Segment Alignment / Gluing	Yellow	Yellow	Yellow	Red	Red	Yellow	Yellow	Yellow
Wet Joint Casting	Yellow	Yellow	Yellow	Yellow	Yellow	Red	Yellow	Yellow
Curing (Overnight)	Yellow	Yellow	Yellow	Yellow	Yellow	Red	Red	Yellow
Installation of External P.T.	Yellow	Yellow	Yellow	Yellow	Yellow	Red	Red	Yellow
Stressing of External P.T.	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow	Yellow	Red



Precast Segmental – Span-by-Span

On Falsework


- Locally available equipment
- Multiple work fronts
- Typically smaller project



Precast Segmental – Full Span

Erection with Launching Gantry

- Typically short spans
- Very high rate of erection
- Factory casting environment - Very high quality
- Min follow up work
- Large temporary loads




Precast Segmental – Full Span

Erection with Launching Gantry

- Typically short spans
- Very high rate of erection
- Factory casting environment - Very high quality
- Min follow up work
- Large temporary loads



Typical Erection Cycle	Duration: 1-Day Cycle (Hours)																		
Description	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23
Delivery New Span from Yard to Erection Site																			
Erection of New Span																			
Return Launching Carrier to Yard																			
Launching Carrier Available for Yard Handling																			
Load New Segment into Launching Carrier																			
Load Transfer from Temporary to Permanent Bearings																			
Prepare Permanent Bearings for Grouting																			
Grout Permanent Bearings																			



Precast Segmental – Full Span

Erection with Launching Gantry

- Typically short spans
- Very high rate of erection
- Factory casting environment - Very high quality
- Min follow up work
- Large temporary loads
- Limited storage (possible)



Precast Segmental – Full Span

Erection with Launching Gantry or Heavy Lift

- Marlins Stadium
- Seven Mile Bridge
- Jamestown Rhode Island



Segmental Construction

- Speed of erection
- Crew efficiency
- High quality
- Many options
- Top down erection possible
minimal disruption to traffic
and surface operations
- Efficient use of forms

**All Possible Through
the innovation of
Post-Tensioning**

